

PROJECT REPORT

REPORT NUMBER: SPR-020425-1 RP2

DATE: 03/03/2025

CLIENT INFORMATION

Sprayroq Inc.
2870 Crestwood Blvd
Irondale, AL 35210
Attn: Casey Alday

SAMPLE DESCRIPTION

One (1) sample of Spray Applied Pipe Liner (SAPL) was received by the client. The sample consisted of various plates approximately one (1) square foot in size. The sample was identified as "Sprayroq Spraywall".

TEST PERFORMED

The sample was tested in accordance with ASTM D638-22, *Standard Test Method for Tensile Properties of Plastics*. Sample preparation of test specimens was performed with a liquid cooled diamond tipped router bit. Testing was performed at a rate of 0.2 in./min.

RESULTS

The tensile properties results are provided in Table 1.

Table 1. Tensile Properties

Specimen	Width (in)	Thickness (in)	Modulus (psi)	Strength at Peak (psi)	Strain at Peak (%)
1	0.500	0.235	868,645	9,324	1.61
2	0.500	0.243	830,064	9,547	1.73
3	0.499	0.241	892,024	9,611	1.71
4	0.499	0.249	842,739	9,559	1.71
5	0.499	0.246	843,531	9,355	1.58
Average	0.500	0.243	855,401	9,479	1.67
SD	0.001	0.005	24,798	130	0.07

Report Written by:



Dan Villarreal
Laboratory Manager

Report Reviewed by:



Steve Ferry
Laboratory Director